

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

4-22

2-010140

API NUMBER: 15-155-21,409-00-00

E/2 E/2 SW, SECTION 34 TOWNSHIP 24 RANGE 9W

OPERATOR LICENSE # 7383 1320 FEET FROM S SECTION LINE
OPERATOR GRADY BOLDING CORPORATION 2970 FEET FROM E SECTION LINE
NAME & P.O. BOX 486
ADDRESS GREAT BEND, KS 67530
LEASE NAME: SCHMUCKER #1
COUNTY: RENO 125.22
WELL TOTAL DEPTH: 3853'
PIPE:
SURFACE CASING: 8 5/8" @ 237'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: L.D. DRILLING INC.

ADDRESS: R.R. 1, BOX 183-B, GREAT BEND, KS 67530 LICENSE: 6039

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 22 MONTH: 4 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: GRADY BOLDING

COMPANY NAME: GRADY BOLDING CORPORATION PHONE: (316) 564-2240

WERE: FILL HOLE WITH HEAVY MUD AND SPOT CEMENT THROUGH DRILL PIPE. SPOT 35 SACKS OF CEMENT AT 1425', 35 SACKS OF CEMENT AT 850', 35 SACKS AT 304', 15 SACKS AT 60', AND 15 SACKS IN RATHOLE.

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { X }

COMPLETED: HOUR: 9:45 DAY: 22 MONTH: 4 YEAR: 1997

ACTUAL PLUGGING REPORT: FILLED HOLE WITH HEAVY MUD AND SPOTTED CEMENT THROUGH DRILL PIPE. SPOTTED 35 SACKS OF CEMENT AT 1425', SPOTTED 35 SACKS OF CEMENT AT 850', SPOTTED 35 SACKS OF CEMENT AT 304', SPOTTED 15 SACKS OF CEMENT AT 60', AND FILLED THE RATHOLE WITH 15 SACKS OF CEMENT.

REMARKS: 60/40 POZ 4% GEL ALLIED #5532

I DID NOT OBSERVE THIS PLUGGING.

Michael R. Wilson

MICHAEL R. WILSON

INVOICED

RECEIVED
KANSAS CORPORATION COMMISSION

DATE MAY 02 1997

MAY 02 1997

INV. NO. 48050

5-297
CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3

REV. 3/90