

8-18-88

To: 1 120128  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER: 15- 057-20,460-0000  
NE NW NW, SEC. 2, T 26 S, R 21 W/E  
6450 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6574  
Operator: Bird Energy, Inc.  
Name & Address: Box 1612  
Dodge City, KS 67801

Lease Name Helen Well # 1  
County Ford 156.00  
Well Total Depth 4800 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 387

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Lobo Drilling Company License Number 5864  
Address Box 877, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 18 Month: 8 Year: 19 88

Plugging proposal received from Ervin Neighbors  
(company name) Lobo Drilling Company (phone) 316-792-7476

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1328-58'  
1st plug at 1360' with 50 sx cement, 2nd plug at 780' with 50 sx cement,  
3rd plug at 410' with 50 sx cement,  
4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1988  
8-23-88  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:30 p.m. Day: 18 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1360' with 50 sx cement,  
2nd plug at 780' with 50 sx cement,  
3rd plug at 410' with 50' sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(if applicable) observe this plugging.

DATE 8-24-88

Signed *Dean Raskin*  
(TECHNICIAN)

INV. NO. 21903