

To: 1 061004
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-17-87
API NUMBER 15- 057-20,399-6000

E/2 NE/4, SEC. 5, T 26 S, R 21 W/E
3960 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9247

Lease Name Klenke Well # 1

Operator: Cincris Energy Company, Inc.
Name & Address 4600 Camelot East
Great Bend, KS 67530

County Ford 157.79
Well Total Depth 4855 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 17 Month: 9 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4855' Perfs at 4777-80'

1st plug sanded back to 4730' and dumped 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pumped 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 17 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4730' and dumped 5 sx cement on top of
sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 800 psi and shut in 500 psi.

SEP 22 1987

9-22-87

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2760' of 5 1/2" casing Wichita, Kansas

(if additional description is necessary, use BACK of this form.)

INVOICED
for ~~_____~~ observe this plugging.

Signed Paul A. Sutter
(TECHNICIAN)

DATE 9-24-87

INV. NO. 18220