

1060918

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4043

Operator: Denver-Alaska Oil Company
Name & Address: 1746 Cole Blvd., Suite 300
Golden, CO 80401

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS, 67524

Company to plug at: Hour: 12:15 p.m. Day: 31 Month: 12 Year: 19 86

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 5540' PBD 4815' 4157' top perf Elevation 2296'GL

1st plug back 4815', 2nd plug sand back to 4100' and dump 4 sx cement on top of sand

through bailer; 3rd plug pump 1 sx hulls, 15 sx gel, 1 sx hulls, and 150 sx light cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 p.m. Day: 31 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug back 4815',

2nd plug sanded back 4100' and dumped 4 sx cement on top of sand through bailer,

3rd plug pumped 1 sx hulls, 15 sx gel, 1 sx hulls, and 150 sx econolight cement.

Maximum pressure 500 psi and shut in 150 psi.

Remarks: Used econolight cement by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
If additional description is necessary, observe this plugging.

DATE 1-5-87

INV. NO. 15752

API NUMBER 15- N/A 15-057-20413-0000

SW NE, SEC. 16, T 26 S, R 21 W/E

3300 feet from S section line

1980 feet from E section line

Lease Name Duesing Well # 1

County Ford 180.05

Well Total Depth 5540 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 400

STATE CORPORATION COMMISSION
JAN 2 1987
CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi
(TECHNICIAN)