

1 080270

15-047-20264-0000 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Not available

TECHNICIAN'S PLUGGING REPORT

C W/2 NW/4, SEC. 34, T 26 S, R 17 WXX

3960 feet from S section line
4620 feet from E section line

Operator License # 5028

Lease Name Roenbaugh Well # 2-34

Operator: Imperial Oil Co.
Name & Address: 720 4th Financial Center
Wichita, KS 67202

County Edwards 150.28

Well Total Depth 4624 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 30 Month: November Year: 19 84

Plugging proposal received from Joe Maes

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4622' PBD 4608' Perfs at 4564-70'

1st plug pump 2 sx hulls and 30 sx cement to bottom, and stop plug at 4050'

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:15 am Day: 30 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4622' PBD 4608' Perfs at 4564-70'

1st plug pumped 2 sx hulls and 30 sx cement to bottom and pushed plug to 4050', 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement

12-5-84
RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 200 psi

Remarks: Recovered 2620' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton (If additional description is necessary, use BACK of this form.)

DEC 05 1984
CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed *J. H. Metz* (TECHNICIAN)

DA 12-11-84
INV. NO. 5907