

To: 1 120844
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-12

API NUMBER 15- 047-20,772-000
N/2. NE NW, SEC. 27, T. 26 S, R. 17 W/2
4950 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30208
Operator: Tri-J Tubulars, Inc.
Name:
Address 125 N. Market, Ste. 1532
Wichita, KS 67202

Lease Name Roenbaugh Well # 6-27
County Edwards 149.17
Well Total Depth 4590 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor DS&W License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2:45 p.m. Day: 12 Month: 10 Year: 19 93

Plugging proposal received from Flip Phillips
(company name) Tri-J Tubulars, Inc. (phone) 316-264-1144

were: 4 1/2" at 4589' w/200 sx cement, PBD 4550', Perfs at 4526-31'

1st plug sand back to 4475' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx wiper plug and pump 125. sx cement.

STATE CORPORATION COMMISSION
RECEIVED
OCT 15 1993

Plugging Proposal Received by Richard Lacey
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 12 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4475' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 250 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3556' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE: 11-2-93

REV. NO. 39087

Signed [Signature] (TECHNICIAN)