

4-20

15-047-21069-0000

To: 1 031007  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 9/15/82

SW SW NW, SEC. 25, T 26 S, R 17 W XX  
2970 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5673

Lease Name Hagewood Well #

Operator: W.L. Kirkman, Inc.  
Name & Address P.O. Box 782290  
Wichita, KS 67278-2290

County Edwards 154.12

Well Total Depth 4742 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 339

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 20 Month: 4 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4741' Perfs at 4348-52, 4537-57'

1st plug pump 2 sx hulls and 35 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:45 p.m. Day: 20 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 35 sx cement,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

RECEIVED STATE CORPORATION COMMISSION

APR 24 1989 4-24-89

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2800 gal casing. (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 4-27-89

Signed Steve Dumont (TECHNICIAN)

FILE NO. 24501 4-20