

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 11 1963

CONSERVATION DIVISION  
Wichita, Kansas

2-11-1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Schuyler of Strata Drilling Inc. has this  
date requested permission to plug the following described well:

Mr. Schuyler guarantees payment of the plugging fee.

Operator's full Name: Strata Drilling Inc.

Complete Address: P. O. Box 355, Great Bend, Kansas

Lease Name: Shriver Well No. # 1

Location: G N/2 NW SE Sec. 23 Twp 29S Rge. 14 (E) (W) W

County Pratt Total Depth 4545 Oil Well

Gas Well Input Well SWD Well D & A  Lost Hole

Mr. Schuyler was instructed to plug the well as follows:

210' of 10 3/4" surface pipe cement circulated with 205  
sacks. Fill hole with heavy mud to 200', 1/4 sack hulls, 1st  
cementing plug and 30 sacks cement. Fill hole with mud to  
40', 1/2 sack hulls, 2nd cementing plug, cement with 15 sacks  
to base of cellar. Rat and mouse bridged and cemented with  
4 sacks.

Very truly yours,

*Arlene Elving*  
Conservation Division Agent