

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

June 4, 1965

RECEIVED
 STATE CORPORATION COMMISSION

JUL 30 1965

6-30-65
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this
 date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Justa Oil Company

Complete Address: P.O. Box 311, Valley Center, Kansas

Lease Name: Hinshaw Well No. 1

Location: NW NW SW Sec. 17 Twp. 24 Rge. 9 (K) (W) X

County Reno Total Depth 3820' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bailey was instructed to plug the well as follows:

Fill hole with sand to 3600' and cement with 5 sacks.

Fill hole with mud to 235'. Set rock bridge from 235' to

225' and cement hole with 25 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with

10 sacks cement.

Very truly yours,

Conservation Division Agent