

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-057-30065-0000

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 23 1966  
9/23/66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Pulley of Mull Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name: Wetzel Well No. 1

Location: G SW SW Sec. 2 Twp. 26 Rge. 21 ~~(E)~~ (W)

County Ford Total Depth 4850' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

8 5/8" to 287' circulated w/ cement. 4 1/2" to 4849' cemented.

Top Perforations 4770' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4700' Mud 4700' to 700'

Spotted 25 sacks cement 700' to 625' Mud 625' to 280'

Spotted 20 sacks cement 280' to 220' Mud 220' to 35'

Plug, Halls & 10 sacks cement 35' to 0'.

Very truly yours,

Edward J. Lewis  
Conservation Division Agent