



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1973  
8-22-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of Okmar has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company

Complete Address: 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name: Klenke Well No. 1

Location: C SW NE Sec. 5 Twp. 26 Rge. 21 (E) (W)

County: Ford Total Depth 4810' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Norwood was instructed to plug the well as follows:

8 5/8" to 367' circulated w/ cement. Mud 4810' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 350'

Spot 35 sacks cement 350' to 250' Mud 250' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent