



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-057-20009-0000

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1968
CONSERVATION DIVISION
Wichita, Kansas
4-23-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Nelson of Walters Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Walters Drilling Co.

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name: Rueb Well No. 1

Location: C NE SE Sec. 6 Twp. 26 Rge. 21 (E) (W)

County Ford Total Depth 4950' Oil Well X

Gas Well X Input Well SWD Well D & A X Lost Hole _____

Mr. Nelson was instructed to plug the well as follows:

8 5/8" to 356' circulated w/ cement. Mud 4950' to 900'

Spotted 100 sacks cement 900' to 550' Mud 550' to 350'

Spotted 30 sacks cement 350' to 250' Mud 250' to 45'

Plug, ~~Hills~~ & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Ford
Conservation Division Agent