



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-657-20041-0000

RECEIVED  
STATE CORPORATION COMMISSION

OCT 30 1972  
10-30-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of Okmar has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Co.

Complete Address: 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name: Torline Well No. 1

Location: C SW NW Sec. 6 Twp. 26 Rge. 21 XX (E) (W)

County: Ford Total Depth 4970' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

8 5/8" to 280' circulated w/ cement. Mud 4970' to 750'

Spot 80 sacks cement 750' to 450' Mud 450' to 280'

Spot 30 sacks cement 280' to 180' Mud 180' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Lewis  
Conservation Division Agent