

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY

Governor
Chairman
Commissioner
Commissioner

Carol J. Larson, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

June 11, 1980

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. DICK DAVIS of H-30 Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. DAVIS guarantees payment of the plugging fee.

Operator's full Name: America Petroleum, Inc. 67501

Complete Address: Box 1459, Hutchinson, Kansas

Lease Name: Alfred Tann Well No. 1

Location: 100' South of CNW NW Sec. 17 Twp. 25 Rge. 4 (E) (W) X

County: Reed Total Depth 391' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. DAVIS was instructed to plug the well as follows:

8 5/8" - 270' - 200 sacks Fluid Standing at 255' Lost Circulation
Squeezed with a total of 300 sacks. Still losing Circulation
Set rock bridge from 255' to 200' and cement hole
to base of cellar with 65 sacks cement.
Cement rat hole with 5 sacks

Very truly yours,

William G. Roman
Conservation Division Agent

JUN 11 1980
6-18-80