

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dec. 3, 1962.

DEC 7 1962
 12-7-62
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Bert Young of Texstar Petroleum Co. has this
 date requested permission to plug the following described well:

Mr. Bert Young guarantees payment of the plugging fee.

Operator's full Name: Texstare Petroleum Co.

Complete Address: 610 Petroleum Bldg., Wichita, Kansas.

Lease Name: O.P. Gilmore Well No. #1

Location: C-SE-NW Sec. 3 Twp. 25S Rge. 4 (E) (W) X

County Reno. Total Depth 40.57 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bert Young was instructed to plug the well as follows:

630' of surface pipe circulated with cement. Hole filled
to 180' with heavy drill mud, 1 sack hulls, 1st cementing plug
and 20 sacks cement. Hole filled to 40' with heavy drill mud,
1 sack hulls, 2nd cementing plug and 10 sacks cement to
base of cellar. Rat. hole bridged and 2 sacks cement.

Very truly yours,

Harmon J. Gustaf
 Conservation Division Agent