



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-1047-10089-0000

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1963

CONSERVATION DIVISION
Wichita, Kansas

12-23-1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Blankenship of Phillips Petroleum Co. has this

date requested permission to plug the following described well:

Mr. Blankenship guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Co.

Complete Address: Box 287, Great Bend, Kansas

Lease Name: Carl "C" Well No. # 1

Location: C SE NW Sec. 18 Twp. 26 Rge. 17 (E) (W) W

County Edwards Total Depth 4625 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blankenship was instructed to plug the well as follows:

362' of 8 5/8" surface pipe, cemented with 200 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, cement
with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent