



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

6-19-82

RECEIVED  
STATE CORPORATION COMMISSION

6-22-82  
JUN 22 1982

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-047-21,049-0000

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Sile Casing of Union Drilling Co. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: F. M. Oil Co. Inc.

Complete Address: 422 Union Center Bldg Wichita Kansas 67202

Lease Name: Fisher Well No. B-1

Location: C-SW-SW-SE Sec. 16 Twp. 26 Rge. 17 (E) (W)

County: Edwards Total Depth: 4690'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Casing was instructed to plug the well as follows:

They cement circulated 325' of 8 5/8" surface casing. The anhydrite was at 1156' top. 1st plug 1120' with 35 sby of cement. 2nd plug at 375' with 35 sby of cement. 3rd plug 40' to 0' with 10 sby of cement. Then circulated 10 sby of cement in rat hole & put 5 sby of cement in water well. The cement was pumped through the drill pipe with hole,

Very truly yours, (over)

Paul A. Luthi  
Conservation Division Agent

full of heavy mud. The cement used was common  
Cement with 3% gel & 2% C.C. The plugging was  
accomplished by sun cementing.

Paul A. Suttis