



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

3 April 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-047-2015-0000

Dear Sir:

Mr. Don Glick of Red Tiger Drilling Co has this date requested permission to plug the following described well:

Operator's Full Name: Gear Petroleum, Inc.

Complete Address: 300 Sutton Place, Wichita, Kansas 67202

Lease Name: Fisher Well No. A2-15

Location: N/2 of N/2 of SE/4 Sec. 15 Twp. 26 Rge. 17 (E) (W)

County: Edwards Total Depth: 4700'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Glick was instructed to plug the well as follows:

They cement circulated 289' of 8 5/8" surface casing. The anhydrite was topped at 1162'. 1st plug at 1080' with 100 sbs of cement. 2nd plug push rubber plug to 275' and pump 40 sbs of cement on top of it. 3rd plug 40' to 0' with 10 sbs of cement on solid bridge. They circulated 10 sbs cement in rat hole & put 3 sbs of cement in water well. The plugging was accomplished by Allied Cementing Co..

Very truly yours,

Paul A. Luther
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

APR 6 1982
4-6-82
CONSERVATION DIVISION
Wichita, Kansas