

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 047-20562-0000 (of this well)

Operator's Full Name Imperial Oil Co.

Complete Address 720 4th. Financial Center, Wichita, Ks. 67202

Lease Name Roenbaugh Well No. 3-34

Location C NE NE Sec. 34 Twp 26s Rge. 17 (E) (W) X

County Edwards Total Depth 4582

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11Am. Day 11 Month 4 Year 1980

The above well was plugged as follows:

444' 8 5/8" casing w/325 sax cement. 4 1/2" casing set at 4581' w/150
sax cement. Preforated at 4567' to 4571'-Sun mixed & pumped 35 sax
common cement in 4 1/2" casing to 4300'-Shut in w/900# pressure-Pull
3725' casing-Sun mixed & pumped 8 sax hulls-125 sax 50/50 posmix
cement w/4% gel & 3% cc to top of casing. Shut in w/200# pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

RECEIVED

APR 14 1980
4-14-80

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 4-14-80

INV. NO. 1927a