

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

RECEIVED FORM CP-3  
STATE CORPORATION COMMISSION 1-8-82  
AUG 04 1982  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15-047-21, 008-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name D. R. Lanch Oil Co.

Complete Address 2215 Broadway Suite 400, Wichita, Kansas 67202

Lease Name Wiles Well No. 3

Location NE-NW-NW Sec. 23 Twp. 25 Rge. 16 (East)(West)

County Edwards Total Depth 4410

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated Well was completed but not produced

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 681

Operation Completed: Hour: 1:15 P.M. Day: 29 Month: July Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

They set 4405' of 4 1/2" production pipe. They plugged it back to 4050' & perforated from 3999' to 4005'. 1st plug sand bottom back to 3950' & dumped 4 sbp of cement on top of sand with baler. 2nd plug pumped through head on 8 5/8". Pumped 5 sbp hulls & 25 sbp gell & released rubber plug & followed it with 150 sbp of cement. They recovered 3619' of 4 1/2" production pipe. The cement used was common cement with 2% gell & 3% C.C. Allied cementing accomplished the plugging.  
Amount of Surface Casing: 388' of 8 5/8" cement circulated with 350 sbp cement

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED

DATE 8-9-82

INV. NO. 843-W