

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

15-047-20716-0000 ✓
API Number 15- - none ✓

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Oil Properties Co. Inc.

Complete Address 403 W. Central Box 335, Andover, Kansas 67002

Lease Name House Well No. 1

Location NW-SE-SE Sec. 28 Twp. 25 Rge. 16W (East) (West)

County Edwards Total Depth 4505'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling Co.

Address Box 176 Chase Kansas 67524 License No. _____

Operation Completed: Hour: 2:30 PM Day: 24 Month: October Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

^{11 surface}
There is 411' of 8 5/8" casing cement circulated. They ran 4500' of 4 1/4" production pipe cemented with 150 lbs cement. Plugged back to 4407'. Perforations were from 4396' to 4404'. 1st plug sandbed back to 4350' with 4 lbs cement. 2nd plug 435' to 0' with 5 lbs hulls 25 lbs gell 125 lbs cement 4 1/2 gell 3% CC. 50/50 sand. There was 3630' of production pipe recovered. Plugging accomplished by Allied Cementing out of Great Bend Kansas. They released rubber plug at 425'. Shut in ^{11 surface}

RECEIVED

OCT 27 1981

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Paul Luther
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas

DATE 11-24-81

INV. NO. 8423-W

10-27-81

146,41