

KANSAS

Handwritten initials

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leben Oil Co.

Complete Address Box 486 Great Bend, Ks

Lease Name English Well No. 1

Location C NE/SE Sec. 28 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4522

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Inc.

Address Box 221 Great Bend, Ks License No. 637

Operation Completed: Hour 1:30 PM Day 6 Month 5 Year 1971

The above well was plugged as follows:

315 ft of 8 5/8 surface pipe cemented with 250 sacks. 4419 ft of 5 1/2
long string cemented with 100 sacks. Top perf. 4392 ft. Sand back
to 4380 ft, 5 sacks cement with bailer. Pulled 2640 ft of 5 1/2. Pumped
2 sacks hulls, 15 sacks gel., 100 sacks cement to surface.

Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 5/13/71

INV. NO. 3067-W