

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leben Oil Co.

Complete Address Box 486 Great Bend, Ks

Lease Name English Well No. 2

Location C SE/SE Sec. 28 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4494

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Inc.

Address Box 221 Great Bend, Ks License No. 637

Operation Completed: Hour 2:30 PM Day 6 Month 5 Year 1971

The above well was plugged as follows:

306 ft of 8 5/8 surface pipe cemented with 250 sacks. 4494 ft of 5 1/2  
long string cemented with 100 sacks. Top perf. 4388 ft. Sand back to  
4375 ft, 5 sacks cement with bailer. Pulled 265 ft of 5 1/2. Pumped  
2 sacks hulls, 15 sacks gel. 100 sacks cement to surface.

Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/13/71  
INV. NO. 3668-W

Signed: A. Russell Baker  
Well Plugging Supervisor