

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAY 13 1963

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name J. E. NewmanComplete Address: Suite 2005 Tower Bldg., Denver, ColoradoLease Name Mayhew Well No. # 1Location SW SW SW Sec. 28 Twp. 25 Rge. 16 (E) (W) WCounty Edwards Total Depth 4500Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Cherokee Drilling Co.Address: Suite 2005 Tower Bldg., Denver, Colorado License No. 350Operation Completed: Hour 10:00AM Day 11th Month May Year 1963

The Above well was plugged as follows:

420' of 8 5/8" surface pipe, cement circulated with 350 sacks. 4498' of5 1/2" long string, cemented with 250 sacks. Plugged back to 4470',Perferated from 4393' to 4398'. Sanded to 4380', cemented with 3 sacks.Fluid level was up in hole. Plug was set at 225', 10' rock bridge, and8 sacks cement and 50# of Cal Seal was mixed and dumped on plug withdump bailer, this was left to set over night. Next morning hole bailedO.K., 12 sacks cement was added to plug. Hole was filled with mud to40', 10' rock bridge, cemented with 10 sacks to base of the cellar.3514' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

5/13/63

INV. NO.

7055-W

Signed:

Audie Elving
Well Plugging Supervisor