

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20,986-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name D. R. Lock Oil Co. Inc.

Complete Address 221 S. Broadway, Suite 400, Wichita, Kansas 67202

Lease Name Parben Well No. D-1

Location 1650' FSL - 290' FEL - SW 1/4 Sec. 29 Twp. 25S Rge. 16W (East) (West)

County Edwards Total Depth 4520'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D. R. Lock Drilling Co.

Address 221 S. Broadway, Suite 400, Wichita, Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 10:00 AM Day: 10 Month: January Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

*There is 369' of 8 1/2" surface casing cement circulated. The Ankylometer was  
toped at 1089'. 1st plug at 900' on solid bridge with 40 skb of  
cement. 2nd plug pushed rubber plug to 330' with 35 skb on  
top of it. 3rd plug on solid bridge 40' to 0' with 10 skb of  
cement. The plugging was accomplished by Allied Cementing  
Co. Inc. They pumped 10 skb of cement in rat hole  
& 3 skb of cement in water well.*

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED  
2-3-82  
9179-W

Signed: Paul Luthin  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas

106.90

106.90