

KANSAS

Form CP-3
RECEIVED
6-14-68
STATE CORPORATION COMMISSION

DEC 26 1978

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -047 -20410 -0000 (of this well)

Operator's Full Name D. P. Sauck Oil Co, Inc

Complete Address 221 S. Broadway Suite 400 Wichita, KS - 67202

Lease Name Parker "B" Well No. 1

Location C - NW - NE Sec. 29 Twp. 25^S Rge. 16 (E) (W) X

County Edwards Total Depth 4490

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Felco Casing Pulling

Address Box 176 Chase Falls - 67524 License No. 683

Operation Completed: Hour 4:15 pm Day 21 Month 12 Year 1978

The above well was plugged as follows:

349' - 8 5/8" Casing w/ 250 sack Cement - 5 1/2" Casing set @ 4488'
w/ 125 sack Cement. Plug back to 4450' Top perf. 4396'
Sand back to 4375' topped sand w/ 5 sack mixed cement
w/ dump bailer. Pull 3550' - 5 1/2" Casing. Allied mixed
& pumped 5 sack hulls - 20 sack gel release plug - mixed
& pumped 125 sp. 60/40 permif. Cement w/ 29 gal 3.7 cc.
to top of Casing

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12-28-78

INV. NO. 8819-W