

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1979

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -047 -20217-0000 (of this well)

Operator's Full Name White & Ellis Drilling, Inc.

Complete Address Box 448 El Dorado, Kansas. 67042

Lease Name Cudney Well No. 1

Location C SW SW Sec. 21 Twp 25S Rge. 16 (E) (W) X

County Edwards Total Depth 4458

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhod Engineering, Inc.

Address Box 698 Great Bend, Ks., 67530 License No. 670

Operation Completed: Hour 11:45 am Day 19 Month 3 Year 1979

The above well was plugged as follows:

362' 8 5/8" casing w/ 275 sax cement. 4 1/2" casing set at 4457' - plug
back to 4399' - Top pref., at 4338' Sand back to 4350' top sand w/ 4
sax mixed cement w/ dump bailer. Pull 3757' 4 1/2" casing. Howco
mixed @ pumped 5 sax hulls - 25 sax gel. Released plug - mixed @ pumped
100 sax 50/50 posmix cement w/ 6% gel @ 4% cal., cholride to top of
casing. Shut in w/ 50# pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: 
Well Plugging Supervisor

INVOICED

DATE 3-28-79
INV. NO. 9318-W