

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name D.R. Lauck Oil Co. Inc.

Complete Address 301 S. Broadway Wichita, Ks

Lease Name Apel Well No. 1

Location C NE/NE Sec. 21 Twp. 25 Rge. 16 (E) W

County Edwards Total Depth 4669

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 E. 6th Ellinwood, Ks License No. 396

Operation Completed: Hour 1:00 PM Day 24 Month 6 Year 1972

The above well was plugged as follows:

329 ft 8 5/8 surface pipe cemented with 220 sacks. 4462 ft 5 1/2 long
string cemented with 150 sacks. Top perf. 4340 ft. Sand back to
4320 ft, 5 sacks cement with bailer. Pulled 3300 ft 5 1/2. Pump 2 sacks
chulls, 15 sacks gel, 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: M. Russell Bihler
Well Plugging Supervisor

INVOICED

DATE 6/29/72
INV. NO. 5937-W