

R

KANSAS

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

DEC 26 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -047 -202360000 (of this well)

Operator's Full Name D. R. Lauck Oil Co, Inc.

Complete Address 321 S. Broadway Suite 400 Wichita, Ks - 67202

Lease Name Steward Well No. 1

Location SW-NE-SE- Sec. 20 Twp. 25^S Rge. 16 (E) (W) X

County Edwards Total Depth 4480

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Felso Casing Pulling -

Address Box 176 Chase, Kans - 67524 License No. 683

Operation Completed: Hour 3-pm Day 21 Month 12 Year 1978

The above well was plugged as follows:

338' 8 5/8" Casing w/ 275 sack Cement. 4 1/2" Casing set @ 4477'
w/ 12.5 sack Cement. Plug back to 4456' Top prof. 4476'
push plug to 4350' Sand back to 4300' topped sand w/
4 sack mixed Cement w/ dump bailer. Pull 2810' 4 1/2"
Casing. All id mixed & pumped 5 sack bulls. 20 sack
gel-release plug - 7 mixed & pumped 12.5 sack 60/40 po mix
Cement w/ 29 gel - 39 cc. to top of Casing -

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12-28-78

INV. NO. 8818-W