


Form CP-3
Rev. 6-26-62


 KANSAS
 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

MAR 31 1966

CONSERVATION DIVISION
 WICHITA, KANSAS

Operator's Full Name Leben Drilling, Inc.

Complete Address: P. O. Box 486, Great Bend, Kansas

Lease Name Trousdale Well No. # 1

Location C SW ^{NE} NW Sec. 18 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4450'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:00AM Day 28th Month March Year 1966

The Above well was plugged as follows:

298' of 8 5/8" surface pipe, cement circulated. 4450' of 5 1/2" long string,
cemented with 150 sacks. Plug back T.D. 4426'. Top perferation 4378'. Bottom
of the hole was sanded to 4350', and cemented with 5 sacks, through the dump
bailer. 2230' of 5 1/2" long string was recovered from the hole. Bridge plug
was pushed in fluid to 285', rock bridge from 285' to 275'. 15 sacks of cemen
t was mixed in a barrel, and put on plug at 275', through the dump bailer,
and let set for five days. Hole was bailed dry, and 10 sacks of cement was
added to the plug. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/31/66

INV. NO. 2960-41