

15-047-21018-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 28 TWP. 25 RGE. 18 E/W
 Location as in quarters or footage from lines:
 NE SW SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Mustang Drilling & Exploration, Inc.
 Lease Name Newsom Well No. #1
 Office Address Box 1609, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed Yes
 Plugging commenced 1-3-84
 Plugging completed 1-12-84
 Reason for abandonment of well or producing formation _____

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom _____ T.D. 4710'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	469'	None
				4-1/2"	4702'	2593.20'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand 4580' and 4 sacks cement. Shot casing at 4000' & 3700', 3500', 3000', 2700', 2500'. Pulled 63 joints of 4-1/2" casing. Sun squeezed well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 125 sacks 50/50 Pozmix cement with 2% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.


STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 James W. Rockhold, Box 698, Great Bend, Kansas 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of January, 19 84

Iona M. Leatherman
 Notary Public.

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION

JAN 20 1984
 1-20-84
 CONSERVATION DIVISION
 Wichita, Kansas