
FORM CP-4

15-047-20505-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plat

Edwards County. Sec. 26 Twp. 25S Rge. 18W E/W
Location as "NE/CNW¼SW¼" or footage from lines
400' FWL and 400' FSL of NE/4
Lease Owner Sterling Drilling Company, et al
Lease Name Brill #1-26 Well No. 1-26
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed May 21, 1979 19
Application for plugging filed May 20, 1979 19
Application for plugging approved May 20, 1979 19
Plugging commenced 10:00 PM - May 20, 1979 19
Plugging completed 12:01 AM - May 21, 1979 19
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production
19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William Owen
Producing formation Depth to top Bottom Total Depth of Well 4720'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	305'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 600' with 50 sacks 50/50 Pozmix, with 3% gel.
Heavy mud to 270' with 40 sacks 50/50 Pozmix, with 3% gel.
Heavy mud to 40', plug and 1/4 sack hulls.
12 sacks to surface; 3 sacks in rathole;
2 sacks in mousehole and 1 sack in water well.

RECEIVED
STATE CORPORATION COMMISSION
5-24-79
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 1979

CHARLES M. HALL
Rice County, Ks.
My Appt. Exp. Jan. 31, 1982

Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - BRILL #1-26
Located: 400' FWL and 400' FSL of NE/4, Section 26-25S-18W,
Edwards County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 14, 1979
COMPLETED: May 21, 1979

TOTAL DEPTH: 4720'

LOG		CASING RECORD
0 - 130	Sand and Gravel	Ran 7 joints 8 5/8", 24# used casing, 292.10 set at 305' K.B. Cemented with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 11:59 PM, 5-14-79.
130 - 307	Clay and Shale	
307 - 2220	Shale	
2220 - 4200	Lime and Shale	
4200 - 4405	Lime	
4405 - 4630	Lime and Shale	
4630 - 4720	Lime	Plugged.