

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-047-20606-00-00

API NUMBER _____

LEASE NAME J.D. Carroll

WELL NUMBER #1 North

_____ Ft. from S Section Line

_____ Ft. from E Section Line
NE SE NW

SEC. 33 TWP. 25 SRGE. 17W (E) or (W)

COUNTY Edwards

Date Well Completed 1-10-80

Plugging Commenced 7-12-88

Plugging Completed 7-15-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Natural Gas Exploration, Inc.

ADDRESS P.O. Box 12108
Wichita, Kansas 67277

PHONE#(316) 721-0548 OPERATORS LICENSE NO. 5019

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4695'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	396'	none
				4-1/2"	4675'	2348'

RECEIVED
STATE CORPORATION COMMISSION
7-21-88
JUL 21 1988

Describe in detail the manner in which the well was plugged, indicating where _____ was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Shot and worked pipe @3010', 2812', 2732', 2531', 2348', pulled a total of 59 joints of 4-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 120 cement, 60/40 pos., 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
Box 347
(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 88

[Signature]
Notary Public

My Commission Expires: _____





200 E. First, Suite 500
~~800 E. First, Suite 500~~
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

January 14, 1980

WELL LOG- - - - - J.D. Carroll No. 1
Location: NE SE NW of Sec. 33-25S-17W, Edwards Co., Kansas

OWNER: Wheatland Oil & Gas, Inc.
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: January 4, 1980
COMPLETED: January 11, 1980

Rotary Total Depth: 4695'

<u>LOG</u>	<u>Casing Record</u>
0 - 40 Surface Sand	Ran 9 jts., 8-5/8", 28#, 8V, Rge 3, used csg., tallied 263' set @ 369
40 - 170 Sand & gravel	KB w/300 sx 60/40 pozmix 2% gel, 3% cc - circulated - plug down @ 9 p.m. 1-4-79
170 - 250 Shale & sand	
250 - 372 Shale	
372 - 500 Sand & shale	
500 - 600 Red Bed	
600 - 950 Red Bed & sand	
950 - 1156 Sand & shale	
1156 - 1188 Anhydrite	
1188 - 2170 Shale & shells	
2170 - 3993 Shale & lime	
3993 - 4053 Lime	
4053 - 4695 Lime & shale	Ran 118 jts., 10.5#, 8Rd., Rge 3, new csg. tallied 4670', set @ 4675KB w/10 bbl salt flush ahead of 200 sx common 10% salt plug down @ 5:30 p.m. 1-11-80 by Allied.