

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,135-00-00

LEASE NAME Joseph Carrol #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NE SW

SEC. 33 TWP. 25 SRGE. 17 W(E) or (W)

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-7-86

Plugging Completed 5-13-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling Bought F/MCO Resources Corp.

ADDRESS Box 347 Chase, Kansas 67524

PHONE # 316 938-2457 OPERATORS LICENSE NO. 6050

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4715'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	487'	none
				4-1/2"	4715'	2556'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3960' and 4 sacks cement. Shot pipe @2925', 2802', 2724', 2640', 2556', pulled a total of 64 joints of 4-1/2" casing. Plugged surface with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 130 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address P.O. Box 347 chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 347 Chase, Ks. 67524

STATE CORPORATION COMMISSION  
MAY 22 1986  
5-22-86  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 21 day of May, 19 86

My Commission expires:



[Signature]  
Notary Public

# KELSO CASING PULLING

Post Office Box 176

CHASE, KANSAS 67524

Phone 938-2457



DARRELL KELSO — Owner

## CONTRACT AGREEMENT

This contract agreement dated February 27<sup>th</sup>, 1986, is between KELSO CASING PULLING and MCO RESOURCES, INC., and concerns the pulling and plugging of the following well by the recommended State Corporation Commission of Kansas procedures:

CARROL #1  
Sec. 33 25S 17W  
Edwards County, Kansas


Bottom Plug: Sand back to 3960', mix and dump (4) four sacks cement with bailer.

Top Surface Plug: Lay down 4-1/2" casing, tie on to 8-5/8" surface pipe and pump (3) three sacks hulls, (15) fifteen sacks gel, (70) seventy sacks cement, (10) ten sacks gel, (1) one sack hulls, release 8-5/8" plug and displace with (100) one-hundred sacks cement.

KELSO CASING PULLING agrees to pull and plug said well according to all state rules and regulations, and also to cut surface pipe off (4) four feet below ground level. Inturn, KELSO CASING PULLING will receive all casing recovered from said well.

MCO RESOURCES, INC. agrees to clean up location, pay all land damages should any occur, and also will pay for the top surface plug which will include water trucks, cementers and welder should one be needed.

SUBMITTED BY:

  
R. Darrell Kelso  
Kelso Casing Pulling

ACCEPTED:

MCO Resources, Inc.

By: 

Title: Manager Drilling & Production

Date: 5 MARCH 86

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1986

CONSERVATION DIVISION  
Wichita, Kansas