


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Edwards County, Sec. 33 Twp. 25S Rge. 17W E/W  
Location as "NE/CNW/SW" or footage from lines  
C NW SE



Locate well correctly on above Section Plat

Lease Owner W. L. Kirkman Inc.  
Lease Name Fatzer Well No. 1  
Office Address Box 18611 Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole  
Date Well completed 5-30-81 19  
Application for plugging filed 5-29-81 19  
Application for plugging approved 5-29-81 19  
Plugging commenced 5-30-81 19  
Plugging completed 5-30-81 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurise Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4976'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud To 1100' 40 Sacks Common 2% Gel 3% CC  
Mud To 470' 35 Sacks Common 2% Gel 3% CC  
Mud To 40' 10 Sacks Common 2% Gel 3% CC  
Bat Hole 10 Sacks  
Mouse Hole 5 Sacks  
Water Well 22 Sacks

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Merckle Drilling Co

STATE OF Kansas COUNTY OF Barton, ss.  
Clyde Merckle (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clyde Merckle  
Box 1382 Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 19 81.

Loretta Barry Notary Public.

My commission expires 3-28-84



RECEIVED  
STATE CORPORATION COMMISSION  
JUN - 3 1981  
6-3-81  
CONSERVATION DIVISION  
Wichita, Kansas

W. L. Kirkman Inc.  
P. O. Box 18611  
Wichita, Kansas 67207

Fatzer #1

C NW SE                      Section 33   Twp. 25S   Rge. 17W

Edwards County

Driller's Log \_\_\_\_\_ Total Depth 4976'

0-----170 Sand  
170----472 Clay & Shale  
472----565 Shale & Sand  
565----1170 Shale & Red Bed  
1170---1184 Anhydrite  
1184---2197 Shale  
2197---2658 Shale & Lime  
2658---2966 Shale & Lime  
2966---3430 Lime & Shale  
3430---4190 Lime & Shale  
4190---4503 Lime  
4503---4670 Lime Chert & Sand  
4670---4976 Lime & Chert

  
Clyde Merckle

RECEIVED  
STATE CORPORATION COMMISSION

JUN - 3 1981

CONSERVATION DIVISION  
Wichita, Kansas