

15-047-20737-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 31 TWP. 25s RGE. 17w E/W
 Location as in quarters or footage from lines:
C SE NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Midwestern Supply Co., Inc.
 Lease Name Fatzer North #2 Well No. _____
 Office Address 300 Patton Road, Great Bend, Ks. 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 6/29/83
 Plugging completed 7/19/83

Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom _____ T.D. 4570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	385'	none
				4 1/2"	4569'	391'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 4480' & ran 4 sacks cement. Shot pipe at 2823' & 2643'. Pipe parted. Recovered 391' of casing. Plugged well with 1 hull, 50 cement, 10 gel, 1 hull, & 100 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 19 83

My Commission expires:



Irene Hoover
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 25 1983
 7-25-83
 CONSERVATION DIVISION
 Wichita, Kansas

W E L L L O G

Well Name: Fatzer North #2
Spud Date: 10-2-80
Completion Date: 10-12-80
Location: C SE NE Section 31-25S-17W
 Edwards County, Kansas

Operator: Wheatland Oil & Gas, Inc.
Contractor: Ramco Drilling Corp.
Casing: 8 5/8" @ 385' w/ 225 sx.
 posmix, 2% gel, 3% CaO
 4 1/2" @ 4569' w/200 sx.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand, Gravel & Shells	0	388
Red Bed & Sand	388	960
Red Bed & Shells	960	1660
Red Bed & Shale	1660	1960
Lime & Shale	1960	4509
Sandstone, Lime, Shale, Churt	4509	4569
Rig Total Depth		4570

RECEIVED
STATE CORPORAT... MISSION
JUN 08 1983
CONSERVATI... JUN
Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER: ss

I certify that the above information is true and correct to the best of my knowledge.

THE RAMCO DRILLING CORPORATION




J. V. Crawford, Vice President

Subscribed and sworn to before me on this 14th day of October, 1980



Sandra Kay May Notary Public

 SANDRA KAY MAY
NOTARY PUBLIC
Butler County, Kansas
My Appt. Exp. 6-5-84

My appt. exp:

**COPY FOR YOUR
INFORMATION**