

LEASE NAME EDWARDS

WELL NUMBER 1-14

970 Ft. from S Section Line

4360 Ft. from E Section Line

SEC. 14 TWP. 24S RGE. 10W (E) or (W)

COUNTY Reno

Date Well Completed 08-02-94

7:30 A.M.

Plugging Commenced 08-02-94

9:30 A.M.

Plugging Completed 08-02-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

Stelbar Oil Corporation, Inc. /

LEASE OPERATOR Grand Mesa Operating Co., Inc.

ADDRESS 155 N. Market, Ste. #500

PHONE# (316) 264-8378 OPERATORS LICENSE NO. #6044

#9855

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 07-27-94 9:00 A.M. (date)

by DON THOMPSON (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? YES

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4020'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from \_\_\_ feet to \_\_\_ feet each set

35 sacks at 1450'; 35 sacks at 950'; 35 sacks at 280'; 25 sacks at 60';

15 sacks in rathole. Used 60/40 Poz 4% gel.

Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142

Address P O BOX 129, STERLING KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: STELBAR OIL CORPORATION

STATE OF KANSAS COUNTY OF RICE, ss.

LEONARD D. DETTER

(Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Leonard D. Detter

(Address) P O BOX 129, STERLING KS 67579

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 94

CHERYL R. DAVIS  
State of Kansas  
My Appl. Exp. Feb. 15, 1997

RECEIVED  
CHERYL R. DAVIS  
Notary Public

USE ONLY ONE SIDE OF EACH FORM

AUG 24 1994

8-24-94

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- EDWARDS #1-14

Located: 970' FSL AND 920' FWL SW/4 of Sec. 14-24S-10W,  
Reno County, Kansas

OWNER: STELBAR OIL CORPORATION INC

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: July 26, 1994

COMPLETED: August 2, 1994

TOTAL DEPTH: 4020' RTD

4018' LTD

## LOG

0' - 85' Surface Soil and Sand  
85' - 235' Red Bed  
235' - 950' Red Bed and Shales  
950' - 1595' Shales  
1595' - 4020' Lime and Shale

## CASING RECORD

Spud at 11:30 AM, 07-26-94. Drilled 235' of 12 1/4" hole. Ran 5 joints 8 5/8" casing. 218.71' pipe set at 230' K.B. Cemented with 200 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 3:15 PM, 07-26-94 by Allied. Good returns. Ticket No. 6781.

Plugged.

## DEVIATION SURVEY

1/4° @ 235'  
1 1/2° @ 3487'  
2 1/2° @ 4020'

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1994

8-24-94

CONSERVATION DIVISION  
WICHITA, KANSAS