

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

	18		

Locate well correctly on above
Section Plat

Reno County, Sec. 18 Twp. 24S Rge. 10 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. 330' EL., 660' NL., N2-NW4

Lease Owner: Tyson Dines

Lease Name: C. Hunter Well No. 4

Office Address: 1210 1st. Nat'l Bk. Bldg., Denver, Colo.

Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole

Date well completed: 11-17-41

Application for plugging filed: 4-12-42

Application for plugging approved: 8-15-42

Plugging commenced: 4-17-42

Plugging completed: 4-25-42

Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Mr. Ruel Durkee

Producing formation: Viola Depth to top: 3772 Bottom: Total Depth of Well: 3798 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD



Formation	Content	From	To	Size	Put In	Pulled Out
Viola Lime	Water	3797	3798	8" 5/8"	205	None
				5 1/2"	3776	3127

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4-17-42 Dumped 20 sacks of cement on bottom before casing was ripped and pulled.

4-24-42 Filled hole to bottom of surface casing with heavy mud.

4-25-42 Set plug at 203'. Dumped 8 sacks of cement. Filled hole with heavy mud to within 18' of cellar floor and dumped 6 sacks of cement; filling casing and cementing cellar floor.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: W.E. Barnes

Address: 217 N. Main Stafford, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.

W. E. Barnes (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) W. E. Barnes

217 N. Main Stafford, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28 day of April, 1942

My commission expires: Aug 4, 1942

Notary Public.



TYSON DINES No. 4 C. HUNTER

330'EL, 660'NL, N2, NW4, 18-24S-10W, Reno County, Kansas

Elevation 1787'.

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
0	117	Sand	2420	2670	Shale & Shells
117	225	Clay	2670	2685	Lime
225	485	Red Bed & Sand	2685	2920	Shale & Shells
485	500	Anhydrite	2920	3220	Lime
500	600	Red Bed Shale	3220	3320	Shale
600	1070	Shale & Shells	3320	3335	Lime
1070	1240	Salt	3335	3385	Lime-Shale & Shells
1240	1360	Shale	3385	3440	Lime & Shale
1360	1820	Lime	3440	3485	Cherty Lime
1820	1850	Shale & Shells	3485	3610	Broken Lime
1850	1940	Lime	3610	3635	Lime
1940	1960	Shale	3635	3762	Shale & Shells
1960	2290	Broken Lime	3762	3767	Misener Sand
2290	2420	Shale	3767	3798	Viola Lime

Total depth 3798'
Water 3797'.

8 5/8" Casing set 205' 100 Sx.,

5 1/2 " Csaing set 3776' 100Sx.,

PLUGGING
 FILE SEC 18-24-R10W
 BOOK PAGE 21 LINE 8

STATE DEPARTMENT OF GEOLOGY
 APR 20 1942
 CONSERVATION DIVISION
 4-29-42