

API NUMBER 15-155-20,991-0000

LEASE NAME Zenith Unit

WELL NUMBER 22

100 Ft. from N Section Line

990 Ft. from W Section Line

SEC. 18 TWP. 24 SRGE. 10 XE or (W)

COUNTY Reno

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-30-97

Plugging Completed 10-3-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Castle Resources Inc. 10-23-97

ADDRESS PO Box 87 Schoenchen, Ks. 67667

PHONE (785) 625-5155 OPERATORS LICENSE NO. 9860

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 2, 1997 (date)

by KCC District #2 (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	248'	
				5 1/2"	3849'	2237'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set Sanded to 3597'. Bailed 5 sks Portland cement. Shot at 2237'. Pulled to 1450'. Pumped 35 sks cement. Pulled to 950'. Pumped 35 sks cement. Pulled to 300'. Circulated cement to surface with 165 sks cement. Pulled the rest of the pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 249 E. Beth Drive Sterling, Ks. 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Jerry Green (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) PO Box 87 Schoenchen, KS 67667

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 97

Katherine Bray  
Notary Public

My Commission Expires: 6-19-2000

USE ONLY ONE SIDE OF EACH FORM

KATHERINE BRAY  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 6-19-2000

Form CP-1  
sed 05-88