

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

#2

API NUMBER 15-155-21,135-0000

LEASE NAME Hurst

WELL NUMBER 1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 4 TWP. 24 RGE. 10 (E) or (W)

COUNTY Reno

Date Well Completed 6-1-90

Plugging Commenced 6-1-90

Plugging Completed 6-1-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Honey Oil Co., Inc.

ADDRESS 401 E. Douglas, Suite 505 Wichita, KS 67202

PHONE# (316) 265-7300 OPERATORS LICENSE NO. 30080

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-30-90 (date)

by Steve Vangleason (KCC District Agent's Name).

to be filed  
Is ACO-1 filed? by operator if not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4015

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1400' w/25 sacks cement thru drill pipe

Next Plug: @ 950' w/25 " " " " " 10 sacks in Mouse Hole

Next Plug: @ 350' w/35 " " " " " 10 sacks in Rat Hole

Top Plug: @ 60' w/25 " " " " " (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lobo Drilling Company

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 4<sup>th</sup> day of June, 1990

Dorothy M. Haque  
Notary Public

My Commission Expires: 5-29-94

DRILLER'S WELL LOG

DATE COMMENCED: May 23, 1990  
DATE COMPLETED: June 1, 1990

Honey Oil Co., Inc.  
HURST #1  
C SW SW  
Sec. 4, T24S, R10W  
Reno County, Ks.

0 - 480' Surface Soil, Shale, Lime,  
480 - 492' Anhydrite  
492 - 2695' Shale & Lime  
2695 - 3115' Lime  
3115 - 3299' Shale & Lime  
3299 - 3652' Lime  
3652 - 3840' Shale, Lime, Sand  
3840 - 4015' Dolomite  
4015' RTD

ELEVATION: 1796 K.B.

Surface Pipe: Set new  
8-5/8", 20# pipe @297'  
w/160 sacks 60/40pcmix  
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*

Subscribed and sworn to before me this \_\_\_\_\_ day of June 1990.

\_\_\_\_\_  
Notary Public

JUN 07 1990  
Rec'd 6-7-90