


WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 11 Twp. 26S Rge. (E) 9 (W)
Location as "NE/CNW&SW¼" or footage from lines SE/4 NW/4 SE/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Reece-Tennant Unit Well No. 1
Office Address 1432 Wichita Plaza Building, Wichita, Kansas, 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 14 1965
Application for plugging filed November 14 1965
Application for plugging approved November 14 1965
Plugging commenced November 14 1965
Plugging completed November 14 1965
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Box 180, Holyrood, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3260 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	202'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Set plug @ 195 ft. w/1/2 sk. hulls and
25 sx. cement. Set plug @ 15 ft. w/15
sx. cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messman-Rinehart Oil Company
Address 1432 Wichita Plaza Building, Wichita, Kansas, 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner)-or-(owner-or-operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
1432 Wichita Plaza Bldg., Wichita, Kansas, 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November 1965

My commission expires December 1, 1968

Barbara J. Scott, Notary Public.

15-155-30089-0000

NO. 1 REECE-TENNANT

Well Record:

Location:	SE/4 NW/4 SE/4, Sec. 13-26S-9W Reno County, Kansas	Commenced:	November 5, 1965
Contractor:	Messman-Rinehart Oil Company 1432 Wichita Plaza Building Wichita, Kansas, 67202	Completed:	November 14, 1965
Operator:	Messman-Rinehart Oil Company 1432 Wichita Plaza Building Wichita, Kansas, 67202	Elevation:	1666' K/B
		Production:	D & A

Casing Record: 10-3/4" @ 202' w/160 sx. com.

*** L O G ***

(Figures indicate bottom of formation)

Sand	35
Sand and Gravel	85
Red Bed and Shells	202
Shale and Shells	1140
Anhydrite	1165
Lime and Shale	1505
Lime	1848
Lime and Shale	2020
Shale and Sand	2418
Lime and Shale	2800
Lime	2925
Lime and Shale	3008
Lime	3207
Shale and Sand	3260 R.T.D.

Sample Tops:

2644'	- Howard (-978)
2767'	- Topeka (-1101)
3191'	- Toronto (-1525)
3199'	- Douglas (-1533)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the abovewell as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By: _____

J. A. Gilliland

Subscribed and sworn to before me
this 19th day of November, 1965

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1968

RECEIVED
STATE GEOLOGICAL COMMISSION

NOV 24 1965

COMMISSION DIVISION
Wichita, Kansas