

15-047-00274-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Edwards County. Sec. 7 Twp. 25 Rge. 20 (E) (W)
Location as "NE/CNW&SW" or footage from lines C NE SE
Lease Owner Sunray DX Oil Company
Lease Name Leona Butler Well No. 1
Office Address 321 West Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 1964
Application for plugging filed Sept. 8, 1964
Application for plugging approved Sept. 8, 1964
Plugging commenced Sept. 6, 1964
Plugging completed Sept. 6, 1964
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Elving
Producing formation Mississippi Depth to top Bottom Total Depth of Well 4863 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

35 Sax cement @ 245'
10 SAX cement 40' to surface
5 Sax in rat hole & mouse hole

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1964
9-15-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. A. Tregellas (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. A. Tregellas
321 West Douglas, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1964

My commission expires July 13, 1967

Men [Signature] Notary Public.

Sunray DX Oil Company
Tulsa, Oklahoma

11 September 1964
Wichita, Kansas

Drig. Contractor: Stickle Drilling Co.
Date Commenced : 22 August 1964
Date Completed : 6 September 1964

Lenora Butler #1
C NE SE 7-25S-20W
Edwards County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Sand and shale	253
Shale	360
Shale and shells	1862
Shale	2408
Shale and lime	2830
Lime and shale	2938
Shale and lime	3278
Lime and shale	3528
Shale and lime	3707
Shale	3799
Lime and shale	4020
Lime	4158
Lime and shale	4246
Lime	4717
Cherty lime	4719
Lime	4760
Lime and chert	4830
Lime	4863 TD

I, R.B. Parriott, hereby certify the above to be a true and complete Driller's Log of the Sunray DX Oil Company's Lenora Butler #1 Well, C NE SE 7-25S-20W, Edwards County, Kansas.


R.B. Parriott


Wanda J. Steakley, Notary Public

My Commission Expires 16 January 1966

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1964

CONSERVATION DIVISION
Wichita, Kansas