


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Edwards County, Sec. 7 Twp. 25S Rge. XX)20 (W)
Location as "NE/CNW/SW" or footage from lines App. C SW SE
Lease Owner Pickrell Drilling Company
Lease Name Russell "B" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 4 19 69
Application for plugging filed December 4 19 69
Application for plugging approved December 4 19 69
Plugging commenced December 4 19 69
Plugging completed December 4 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elyng
Producing formation Depth to top Bottom Total Depth of Well 4738 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	325'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 450' w/50 sacks cement, plug @ 300' w/25 sacks, plug @ 40' with 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1969
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas (Address)

Subscribed and Sworn to before me this 10th day of December, 19 69

My commission expires May 10, 1970



L. M. Whiting
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 11/22/69

Rotary Drilling Completed 12/4/69

LOCATION: Russell "B" # 1, App. C SW SE Section 7-25S-20W
Edwards County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 14 Jts. 28# 8-5/8" surface casing set @ 325' KB. Cemented with 200 sacks. Completed 5 PM November 22, 1969. Circulated.

No oil string run. D & A. Plugged 12:30 AM December 4, 1969.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

100	Sand & Sandy Clay	C.F.S.
325	Shale & Shells	4124
480	Shale	4154
595	Sand	4162
925	Shale & Red Bed	4278
1000	Sand	4626
1407	Shale - Red Beds	4705
1444	Anhydrite	4710
1930	Shale & Shells	4718
2250	Shale	4738
2330	Shale & Lime	
2610	Lime & Shale	S.L.M.
2940	Lime	Strap 3518.07
3000	Lime & Shale Streaks	Board 3516.22
3048	Shale & Lime	1.85 No Corr.
3355	Lime & Shale	
3919	Shale & Lime	Slope Tests
4124	Lime & Shale	2000
4705	Lime	2500
4738	Mississippian, RTD	3000
		3500
		4000
		4500

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1969
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in regard of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS
COUNTY OF SEDGWICK ss.:
On this 10th day of December, 1969, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and that he is free and lawfully acting and doing for such company, for the uses and purposes therein set forth.
Given in my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
L.M. Whiting Notary Public