

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 31 Twp. 25S Rge. 19W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE NW


Lease Owner Sterling Drilling Company, et al
Lease Name Moletor #1 Well No. 1
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed November 30, 1977 19
Application for plugging filed November 29, 1977 19
Application for plugging approved November 29, 1977 19
Plugging commenced 6:30 AM, November 30, 1977 19
Plugging completed 8:15 AM, November 30, 1977 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 1900'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section List

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	292'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION

DEC 02 1977
12-2-77
CONSERVATION DIVISION
Wichita, Kansas

Filled hole with heavy mud.
Heavy mud to 550' with 40 sacks thru
drillpipe; heavy mud to 280' with 25 sacks
thru drillpipe, with solid bridge at 40' with
plug, hulls and solid bridge; 12 sacks to
surface and 3 sacks in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of December, 1977

CHARLES HALL--NOTARY PUBLIC
My Commission Expires Jan. 9 1978

Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- MOLETOR #1

Located: NE NW, Section 34-25S-19W, Edwards County,
Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 22, 1977

COMPLETED: November 30, 1977

TOTAL DEPTH: 4900'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 41 Sand and Surface Soil	Ran 7 joints new 23#, 8 5/8" casing, 280.70' set at 292' K.B. with 250 sacks 60/40 Pozmix with 3 1/2 cc. Plug down at 11:30 PM, 11-22-77, by Howco.
41 - 295 Sand and Shale	
295 - 738 Shale and Sand, Red Bed	
738 - 750 Blane Section	
750 - 1318 Red Beds	
1318 - 1325 Anhydrite	
1325 - 1875 Shale	
1875 - 2131 Shale, Shells and Lime	
2131 - 4170 Shale and Lime	
4170 - 4645 Lime	
4645 - 4715 Lime and Shale	
4715 - 4750 Mississippi	
4750 - 4815 Chert and Cherty Lime	
4815 - 4881 Lime and Shale	
4881 - 4900 Cherty Lime (Viola)	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

DEC 02 1977

CONSERVATION DIVISION
Wichita, Kansas