


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division,  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Edwards County. Sec. 23 Twp. 25 Rge. 19 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines C NE SW  
Lease Owner Pickrell Drlg. Co.; Wichita, Kansas 67202  
Lease Name Arensman 'C' Well No. # 1  
Office Address 705 Fourth National Bank Building  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Jan. 20 19 71  
Application for plugging filed March 31 1971  
Application for plugging approved March 31 1971  
Plugging commenced April 1 1971  
Plugging completed April 19 1971  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4665 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	284	None
				4 1/2	4654	4226

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

April 1, 1971 Plugged off bottom. Dumped sand to 4600'. Mixed and dumped 4 sx of cement to 3550'.  
April 19, 1971 Plugged off top. Globe Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing; 2 sx of hulls, 15 sx of gel, released plug and 100 sx of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
5-17-71

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Russ Casing Pulling, Inc.  
Address P. O. Box 1082; Great Bend, Kansas 67530


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of May, 19 71

My commission expires January 19, 1973



Esther Lamore  
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 1/8/71

Rotary Drilling Completed 1/20/71

LOCATION: Arensman "C" No. 1 C NE SW Section 23-25S-19W,  
Edwards County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 12 Jts. 8-5/8" surface casing set @ 283' KB. Cemented w/190 sacks cement. Completed 9:00 P.M. Circulated.

Run 146 Jts. 4-1/2" casing set @ 4654'. Cemented with 125 sacks common cement. Plug down 3:00 P.M. January 20, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

120	Sand		<u>C.F.S.</u>
250	Shale & Sand Streaks		4110.
500	Shale		4138
800	Red Beds		4140
850	Sand		4250
1165	Red Beds - Shale		4305
1280	Shale		4400
1303	Anhydrite		4433
1665	Shale & Shells		4685
2070	Shale		4655
2210	Shale & Lime		4659
2570	Lime & Shale		4665
2848	Lime		
3280	Lime - Shale		<u>S. L. M.</u>
3560	Shale & Lime	Board	4170.23
3835	Lime - Shale	Strap	4166.79
3870	Lime		3.44 Short
3932	Shale & Lime		
4070	Shale		
4665	Lime, RTD		<u>Slope Tests</u>
			2000
			2500
			3000
			3500
			4000
			4500

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 3 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By *C. W. Sebitts*  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 25th day of January, 1971, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

*Esther Lamone*  
Esther Lamone Notary Public