

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-047-20292-00-00
API NUMBER

LEASE NAME Wilson

WELL NUMBER #1-29

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 29 TWP. 25 RGE. 18W (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 12/12/88

Plugging Completed 12/16/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

250 N. Water #300

ADDRESS Wichita, KS 67202

PHONE# (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5036

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	272	none
				4 1/2	4382	2495

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4180, dumped 4 sacks cement, shot @3021', 2737', 2495', plugged surface with 400# hulls, 10gel, 50 sacks cement, 10 gel, 100# BuVls, 120 sacks 60/40 poz, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 88

Jane Torrey
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
12-21-88
DEC 21 1988

CONSERVATION DIVISION
Wichita, Kansas

Kockwood
(1/23)

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Wilson #1-29
C SE SE Sec 29-25S-18W
Edwards County Kansas

Commenced: 10-21-77

Completed: 11-11-77

OPERATOR: MURFIN DRILLING CO.

From	Depth to	Formation	Remarks
0	228	Sod-Sand	Ran 7 jts of 28# 8 5/8" csg set @ 272' Cemented w/ 2% Gel - 3% CC PD @ 6:25 p.m. 10-21-77
228	278	Shale-Shells	
278	560	Shale	
560	1000	Sand-Redbed	Ran 101 jts of 9 1/2# 4 1/2" csg set @ 4382' w/float @ 4348' Cemented w/125 sks Class A w/10% Salt 3/4 of 1% CFR-2 50 sks Class A Latex PD @ 1:45 p.m. 11-11-77
1000	1758	Sand-Shale	
1758	2320	Shale-Shells	
2320	2527	Shale-Lime	
2527	2580	Lime w/shale	
2580	2970	Shale-Lime	
2970	3830	Lime-Shale	
3830	3925	Lime	
3925	4030	Lime-Shale	
4030	4150	Lime	
4150	4395	Lime-Shale	
4395	4644	Lime	
4644	4680	Cherty Lime	
4680	4824	Lime	
4824	4907	Lime-Chert	
4907	4960	Lime-Shalk	
4960	5036	Lime	
	5036 - TD		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 18th day of November, 1977.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC