

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County, Sec. 36 Twp. 24 Rge. (E) 5(W)

Location as "NE/CNW/SW" or footage from lines 90 50 07 SE SE NW
Lease Owner Leben Drilling, Inc.
Lease Name Gilmore "A" Well No. 1
Office Address 905 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 10 19 56
Application for plugging filed November 10 19 56
Application for plugging approved November 10 19 56
Plugging commenced November 10 19 56
Plugging completed November 10 19 56
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel E. Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3867 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	684'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 350', set 15 sacks of cement, heavy mud to 40' and cemented to top with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James M. Battin (employee of owner) ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Battin
905 Central Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of November, 19 56

My commission expires July 10, 1957

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1956
Wichita, Kansas
11-14-56
Notary Public.

PLUGGING
FILE SEC 36 T. 24 R. 5W
BOOK PAGE 115 LINE 24

CONTRACTOR'S WELL LOG

Leben Drilling, Inc.
 #1-A Gilmore
 90' South of SE SE NW of 36-24S-5W
 Reno County, Kansas

0	365	Clay and Shells
365	540	Shale and Lime Shells
540	675	Shale and Lime
675	684	Anhydrite
684	732	Anhydrite
732	753	Anhydrite and Chalk
753	805	Lime and Shale
805	2180	Shale and Lime
2180	2395	Lime and Shale
2395	2680	Shale and Lime
2680	2745	Lime and Shale
2745	2815	Shale and Lime
2815	2960	Lime and Shale
2960	3000	Lime
3000	3415	Shale and Lime
3415	3500	Lime
3500	3550	Mississippi Lime
3550	3610	Lime
3610	3725	Shale and Lime
3725	3730	Sand
3730	3810	Shale and Lime
3810	3830	Lime and Shale
3830	3848	Viola
3848	3853	Simpson
3853	3867	Simpson
	3867	<u>Rotary Total Depth D & A</u>

COMMENCED: October 28, 1956
 COMPLETED: November 10, 1956
 SURFACE CASING:
 8 5/8" 684' w/400 sks.
 cement.

State of Kansas)
 County of Sedgwick) ss:

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Gilmore #1-A, 90' South of SE SE NW of Section 36-24S-5W, Reno County, Kansas, as reflected by the files of Leben Drilling, Inc..

James M. Battin
 James M. Battin

Subscribed and Sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 13th day of November, 1956.

James Thomas

My commission expires July 10, 1957

RECEIVED
 NOV 14 1956
 CONSERVATION DIVISION
 Wichita, Kansas

11-14-56

PLUGGING
 FILE: SEC. 36 T. 24 R. 5W
 BOOK PAGE 115 LINE 24