


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno County, Sec. 6 Twp. 24S Rge. 6 (E) E (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner Osage Oil & Gas, Etal  
Lease Name Benton Well No. 1  
Office Address Box 334, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 12 1958  
Application for plugging filed " 19"  
Application for plugging approved " 19"  
Plugging commenced " 19"  
Plugging completed " 19"  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hapel, Pretty Prairie, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4200' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	246	8 5/8"	246	None
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with mud from 4200' to 240': Set 20 Sacks Cement on Bridge Plug at 240':  
Filled mud to 40': Set 10 Sacks of cement on Bridge Plug at 40' and filled to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rex & Morris Drilling Company  
Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure  
Box 334, El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1958

My commission expires August 8, 1962  
Elizabeth Deschner Notary Public.

RECEIVED  
OCT 28 1958  
10-28-58  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 6 T 24 R 6W  
BOOK PAGE 138 LINE 35

BENTON WELL # 1

OSAGE OIL & GAS CO, INC., et al.

Total Depth	- 4200	Location	- NW NW SE
Contractor	- Rex & Morris Drilling Co.	Section	- 6-24S-6W
Commenced	- October 1, 1958	Reno County, Kansas	
Completed	- October 12, 1958		
Initial Production	- D & A		

Casing Record:  
8 5/8" @ 246' w/200 Sacks

FORMATION	DEPTH
Surface Hole	246
Shale and Shells	920
Lime and Shale	2080
Shale and Lime	2675
Lime	2793
Lime and Shale	2895
Shale and Lime	2940
Sand	3000
Shale and Lime	3014
Lime	3469
Lime and Shale	3573
Conglomerate	3681
Chat and Lime	3777
Lime	3795
Lime and Shale	3850
Shale	3945
Shale and Lime	4023
Lime	4090
Shale and Lime	4148
Lime	4200

T. D.  
(Schlumberger)

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Koontz  
Paul D. Koontz, Geologist

STATE OF KANSAS  
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 27<sup>th</sup> day of October, 1958

Elizabeth Deschner  
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1962

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1958

PLUGGING

FILE SEC. 6 T. 24 R. 6W  
CONSERVATION DIVISION BOOK PAGE 138 LINE 35

10-28-58