


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

RENO County. Sec. 28 Twp. 24 Rge. 5 (E) W (W)
Location as "NE/CNW/SE" or footage from lines NW NW SE
Lease Owner SOLAR OIL COMPANY
Lease Name GARVER Well No. 1
Office Address 1117 Union National Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 15 1963
Application for plugging filed May 15 1963
Application for plugging approved May 15 (verbally) 1963
Plugging commenced May 15 1963
Plugging completed May 15 1963
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3427 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	237'	10 3/4"	237'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set rock bridge @ 1800'. Rock bridge @ 485'. Rock bridge @ 280'
with 35 sacks of cement. Plug @ 30' with 15 sacks of cement.
5 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1963

6-5-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HARMS DRILLING COMPANY
Address P.O. Box 488 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
ALLAN HARMS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms

P.O. Box 488 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 1963

Helen E. Gearhart
Helen E. Gearhart Notary Public.

My commission expires 1-22-66.

D R I L L E R S L O G

COMPANY: SOLAR OIL COMPANY
FARM: GARVER #1
COMMENCED: MAY 3, 1963

NW NW SE SECTION 28-24-5W
RENO COUNTY, KANSAS
COMPLETED: MAY 15, 1963

ELEVATION: 1547 RB

0 - 30	Soil
30 - 40	sand
40 - 160	red bed
160 - 420	shale & shells
420 - 655	salt & shale
655 - 1618	lime-shale
1618 - 1632	sand
1632 - 2575	lime-shale
2575 - 2682	shale-lime
2682 - 3150	lime
3150 - 3406	shale-lime
3406 - 3427	Mississippian
3427	Total depth

SET 237' of 10 3/4" surface pipe. Cemented with 225 sacks of cement with 2% gel and 2% calcium chloride.

TOPS:	TARKIO SAND	-	1618
	HEEBNER	-	2494
	BROWN LIME	-	2682
	LANSING - K.C.	-	2710
	MISSISSIPPI	-	3406

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1963
6-5-63
CONSERVATION DIVISION
WICHITA, KANSAS

DRY, plugged, and abandoned.

A F F I D A V I T

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, ALLAN HARMS of the Harms Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms
ALLAN HARMS

Subscribed and sworn to before me this 24th day of May, 1963.

Helen E. Gearhart
Helen E. Gearhart - Notary Public

My commission expires: 1-22-66.