


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 28 Twp. 24S Rge. 5 (W)
Location as "NE/CNW%SW%" or footage from lines Gen. E/2 SE/4 SE/4
Lease Owner Richard S. Davis
Lease Name Freddie Yoder Well No. 1
Office Address 1023 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 12 19 67
Application for plugging filed Verbal Approval 19
Application for plugging approved Verbal Approval 19
Plugging commenced November 12 19 67
Plugging completed November 12 19 67
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	75'	None
				8 5/8"	653'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,093 feet (rotary total depth) to 240 feet. Set bottom plug at 240 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1967
11-15-67
OFFICE OF THE CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 200 N. Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
Arlo B. Romer
200 N. Main St., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November, 19 67

My commission expires April 21, 1971
Martha Hartpence
Notary Public.

15-155-20029-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Richard S. Davis

SEC. 28 T. 24S R. 5W
LOC. E/2 SE/4 SE/4

FARM Freddie Yoder NO. 1

COUNTY Reno
KANSAS

TOTAL DEPTH 3,093'


COMM. October 31, 1967

COMP. November 12, 1967

SHOT OR TREATED:

CONTRACTOR H-30, Inc.

ISSUED



CASING

20 10
15 8 -5/8" 653' cemented W/185 sacks cement VARIATION 1,546 KB
12 6
13 -3/8" 5
/ 75' cemented W/50 sacks cement

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

SAMPLE TOPS

Surface Soil & Red Bed	77		
Red Bed	170	Topeka	2,115 - 569
Red Bed, Clay & Shale	394	Heebner	2,465 - 919
Salt	424	Douglas	2,492 - 946
Salt & Shale	553	Brown Lime	2,681 -1,135
Salt	622	Lansing	2,696 -1,150
Lime & Shale	655	Rotary T.D.	3,093 -1,547
Shale & Shells	951		
Shale & Lime	1,049		
Shale	1,126		
Lime	1,470		
Lime & Shale	1,973		
Lime	2,015		
Lime & Shale	2,117		
Lime	2,455		
Lime & Shale	2,490		
Shale & Sand	2,665		
Lime	2,795		
Lime & Shale Streaks	2,890		
Lime	2,935		
Lime & Shale Streaks	3,025		
Lime	3,093		
Rotary Total Depth	3,093		

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1967
11-15-67
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 14th day of November, 1967.

Martha Hartpence
Martha Hartpence - Notary Public

My Commission Expires:
April 21, 1971